



DD2 Site Preparation Checklist

Thank you for purchasing an Agilent instrument. To get you started and to assure a successful and timely installation, please refer to this specification or set of requirements.

Correct site preparation is the key first step in ensuring that your instruments and software systems operate reliably over an extended lifetime. This document is an information guide AND checklist prepared for you that outlines the supplies, consumables, space and utility requirements for your equipment for your site.

For additional information about our solutions, please visit our web site at <http://www.chem.agilent.com/en-US/Pages/HomePage.aspx>

Customer Responsibilities

Make sure your site meets the following prior to the installation date using the checklist below. For details, see specific sections within this document, including:

- The necessary laboratory space is available.
- The lab requirements **as listed in this checklist and the “DD2 MR Installation Planning Guide”**
- The required operating supplies necessary for the product and installation
- Please consult Other/Special Requirements section below for other product-specific information
- If Agilent is delivering installation and familiarization services, users of the instrument should be present throughout these services; otherwise, they will miss important operational, maintenance and safety information.
- For more details, please consult the product-specific site prep manual “DD2 MR Installation Planning Guide”

Important Customer Information

1. If you have questions or problems in providing anything described as a *Customer Responsibilities* above, please contact your local Agilent or partner support/service organization for assistance prior to **delivery. In addition, Agilent and/or it's partners reserve the right to reschedule the installation** dependent upon the readiness of your laboratory.
2. Should your site not be ready for whatever reasons, please contact Agilent as soon as possible to re-arrange any services that have been purchased.
3. Other optional services such as additional training, operational qualification (OQ) and consultation for user-specific applications may also be provided at the time of installation when ordered with the system, but should be contracted separately.



Selecting the MR Installation Site

Ensure the following factors have been taken into account for the MR system site selection:

- Verify the site configuration with an Agilent representative before designing the layout
- Consider the fringe field effects on the surroundings
 - Ensure that sensitive equipment, pace makers, ferromagnetic objects, etc., are outside the 5 gauss line
 - Consider the stray field effects on areas or floors above and below the magnet
 - Be mindful of safety hazards of large, unrestrained stationary ferromagnetic objects
 - Be mindful of homogeneity disturbances caused by
 - Moving ferromagnetic objects such as elevators, pallets, trams, etc.
 - Environmental magnetic fields
 - Ensure sufficient space layout so the console, workstation, and power bay (if present) will be outside the 5 gauss line.
 - Site construction materials affecting the magnetic field such as steel beams, steel studding, etc
- Ensure site accessibility requirements have been met (pallet/forklift transport, cryogen dewars, emergency routes, system crates, etc)
- Ensure system can be easily accessed for operation, maintenance, and cryogenic service
- Ensure the ceiling requirements have been met taking into account the system, magnet, and accessory dimensions, including any possible floor-plates.
- Ensure the following floor requirements are met:
 - Structural floor loading requirements for all system components during and after installation
 - Floor leveling and covering
 - Floor vibrations are within stated specs
- Ensure potential EMI requirements have been met taking into account power lines, transformers, elevators, local trams, etc.
- Ensure the site meets RF interference requirements
 - External sources such as TV, radio, cellular
 - Other NMR spectrometers operating at the same frequency
- Ensure ventilation requirements have been met
-

Special Notes:

1. **Ensure all lab requirements are met before the “Ship By” date on the order acknowledgement to prevent installation delays**



Environmental Conditions

Operating your instrument within the recommended lab requirements insures optimum instrument performance and lifetime.

- Ensure the site temperature requirements are met as stated below
- Ensure the site humidity requirements are met as stated below
- If needed, ensure stringent site stability requirements are met
- Ensure no direct sunlight falls on the any system component, especially the magnet
- Ensure ventilation requirements are met
 - If necessary, install recommended oxygen and air flow sensors
 - If required, ensure quench piping is installed

Special Notes:

1. Performance can be affected by sources of heat & cold e.g. direct sunlight, heating/cooling from air conditioning outlets, drafts and/or vibrations.
2. **The site's ambient temperature conditions must be stable for optimum performance.**

| Stability Requirements Type | Operating temp range °C (F) | Operating humidity range (%) | Temperature Stability °C (F) |
|---|-----------------------------|------------------------------|------------------------------|
| Standard: For 600 MHz and below | 17 - 24 deg (60 – 75) | 20 - 80 | +/- 1 (+/- 1.8) |
| Stringent: For 700MHz and above OR long-term stability required | 18 – 25 deg (63 – 77) | | +/- 0.5 (+/- 1) |



DD2
Site Preparation Checklist



Power Consumption

| Component | Required Outlets | Electrical Requirements (Vac) (single phase at 50-60 Hz) | Current Rating (A) |
|--|------------------|---|--------------------|
| Two-cabinet console | 1 | 200,208,220,230,240 | 20 |
| Pneumatics Router | 1 | 120/240 | |
| Host PC and peripherals | 6 | 120 240 | 15 7.5 |
| 7510-AS | 1 | 120 240 | 15 7.5 |
| 7600-AS | 1 | 120 240 | 15 7.5 |
| VAST autosampler | 2 | 120 240 | 15 7.5 |
| Accessories and test equipment | 6 | 120 240 | 20 10 |
| Solid-state power cabinet (CH 1 and 2) | 1 | 220 | 30 |
| Solid-state power cabinet (CH 3 and 4) | 1 | 220 | 30 |
| Micro-imaging module cabinet | 1 | Refer to the DD2 MR Installation Planning Guide | |
| Third cabinet for 700 – 1000 MHz | 1 | 220 | 30 |
| VT CP/MAS module | 1 | 110-125 220-240 | 15 7.5 |
| Diffusion (L500) | 1 | 3-phase 208 – 240 3-phase 380 - 415 | 10 5 |
| Cold Probe system | | Refer to Cold Probes Installation and Operation manual | |
| | | | |

Special Notes:

- 1) For details consult the site planning manual “DD2 MR Installation Planning Guide”
 - a. Observe the voltage and frequency line variations
 - b. Consider a UPS if necessary



DD2
Site Preparation Checklist



Laboratory Gas Supply Requirements

Air or Nitrogen Gas

| System Configuration | Pressure psig (kPa) | Flow Rate LPM (SCFH) |
|---|---------------------|----------------------|
| Normal operation | 80 (585) | 54 (114) |
| During Eject | 80 (585) | 75 (159) |
| System with gHX Nano probe | 80 (585) | 45 (95) |
| System with Doty probe, Solid-state MAS spinning | 90 (620) | 50 (106) |
| System with Agilent solids probe, solid-state VT, and probe purge | 80 (585) | 169 (360) |
| System with Agilent solids probes, solid-state MAS spinning | 90 (620) | 141 (300) |

Special Notes:

- 1) For 200-900 systems liquids, micro-imaging or liquids & micro-imaging with no options the air source is needed for spin, probe/shim cooling, VT, eject, and anti-vibration legs.
- 2) Engineer will supply air filter/coalescing oil filter for liquids systems
- 3) Other gas supply considerations/requirements:
 - Ensure the supplied air has a dew point of -40 C min or -60 C min with an FTS chiller
 - Consider using nitrogen gas for less-than-ambient temperature experiments
 - Consider Air-dryers in high humidity areas
 - For solids systems review special gas supply requirements
 - Ensure meeting holding tank requirements if using a portable compressor
 - Consider separate air sources for system options:
 - o Anti-vibration table
 - o Solids options such as CRAMPS and CP/MAS have special dewpoint, oil removing, and filtration air requirements

AC power and air conditioning requirements

| System | Power (kW) | Surge Current (A) | Power Factor | BTU/hr |
|---|------------|-------------------|---------------|--------|
| 300-600 MHz 2-bay standard | 0.7 | 85 | 0.925 leading | 2400 |
| 700-900 MHz 3-bay, 4CH liquids | 2.3 | 78 | 0.925 leading | 7850 |
| Host work station, monitor, peripherals | 0.9 | | | 3100 |
| Autosampler | 0.18 | | | 615 |
| Additional solids high-band channel | 0.82 | | | 2800 |
| Additional extra high power, solids, low band channel | 1.32 | | | 4500 |
| Additional liquids RF channel | 0.5 | | | 1700 |
| Micro-imaging module | 1.5 | | | 5120 |
| Solids Accessory cabinet | 0.02 | | | 68 |



Other/Special Requirements

Before the installation takes place:

- Ensure a moving crew is provided to move the crates from the dock to installation site for 600 NB magnets and lower (not for 600WB magnets and higher)
- If feasible provide telephone and Internet access in the spectrometer lab
- Ensure precautions are taken against electrostatic discharges to prevent system damage.
- Provide the necessary network information as indicated in the planning guide.
- Ensure the required installation supplies and equipment are ready prior to the start of the install
 - Liquid helium and nitrogen
 - Gas helium and nitrogen
 - Face mask, gloves, heat gun, and non-ferromagnetic ladder
 - Hoist
- Check the SHIP BY date on the Agilent Order Acknowledgment form, and use this date as a target for completing installation preparations.
- Perform the post-delivery inspection and report any damage upon receipt of the system boxes and crates as indicated in the Installation Planning Guide.
- Ensure all checks in this document and requirements in the Installation Planning guide have been met prior to scheduling the installation

Once the magnet installation has begun, please ensure the following:

- Measure the stray magnetic field with a gauss meter after the magnet is fully energized
- Post the provided signs warning of magnetic field hazards



DD2
Site Preparation Checklist

Document Control Logs

Revision Log:

| Revision | Date | Reason For Update |
|----------|-----------|-------------------|
| A | 4/15/2011 | Released Version |
| | | |
| | | |
| | | |
| | | |

Approval Log:

| Revision | Approver(s) | Title of Approver |
|----------|----------------|--------------------------------|
| A | Kenneth Kezeor | Manager, NMR Technical Support |
| | | |
| | | |
| | | |
| | | |